

CITY OF RAYMORE

100 Municipal Circle · Raymore, MO. 64083
Phone · 816-892-3045 · Fax · 816-892-3093



ADDENDUM NO. 1

2020 Stormwater Improvements
Project #20-350-201

All plan holders are hereby notified and agree by signature below, that the proposal includes consideration of the following changes, amendments, and/or clarifications and costs associated with these changes and are included in the proposal.

Addendum No. 1 - Clarification.

- 1. The unit for 2" Surface Asphalt on Olive / Jefferson Culvert should be SY, not LF. Revised Bid Proposal Form E attached.
- 2. The City would consider cast-in-place for the wing walls with engineered, stamped plans submitted for approval.
- 3. Ridgewood Drive inlet replacement is only for the inlet top, throat, and sidewalk behind it. The inlet box stays in place. See attached photo for reference.

Pre-bid Attendees:

J&N Utilities	Westland Construction	Tasco LLC
Redford Construction	JM Fahey Construction	Jim Richardson Construction
Breit Construction		

Any other questions regarding this proposal shall be submitted to Kim Quade, CPPB by e-mail at kquade@raymore.com or by phone at (816) 892-3045. There will be no questions allowed after July 20th, 2020 at 5 p.m.

I hereby certify that the above have been considered and associated costs have been included in this bid.

Company Name: _____

By: _____

Title: _____

Address: _____

City, State, Zip: _____

Date: _____ Phone: _____

Signature of Bidder: _____

ADDENDUM MUST BE SUBMITTED WITH BID

****REVISED** BID PROPOSAL FORM E – Project No. 20-350-201**

**2020 Stormwater Improvements Project
Base Bid**

Crest Drive Inlet Replacement

Bid Item	Units	Estimated Quantities	Unit Price	Total Est. Price
Curb Inlet (10 x 5)	Each	1	\$	\$
CG-2 Curb	LF	40	\$	\$
42" (HDPE)	LF	16	\$	\$
Tie into Existing J. Box	Each	1	\$	\$
Sawcut	LF	20	\$	\$
Sidewalk	SF	200	\$	\$
2" Type 2 Asphalt	SY	12	\$	\$
Restoration (Seed)	SY	20	\$	\$
SUB TOTAL				\$

Olive/Jefferson Culvert

Bid Item	Units	Estimated Quantities	Unit Price	Total Est. Price
15" HPDE	LF	36	\$	\$
15" HDPE FES	EA	2	\$	\$
Flowable Fill	CY	10	\$	\$
Grading	SY	50	\$	\$
2" Surface Asphalt	SY	10	\$	\$
Seed/Erosion Control Mat	SY	20	\$	\$
SUB TOTAL				\$

Aspen Drive Culvert

Bid Item	Units	Estimated Quantities	Unit Price	Total Est. Price
15" HPDE	LF	25	\$	\$
15" HDPE FES	EA	2	\$	\$
Grading	SY	200	\$	\$
Seed/Erosion Control Mat	SY	200	\$	\$
¾" Gravel	Ton	2	\$	\$
SUB TOTAL				\$

Silvertop Lane Wing Walls

Bid Item	Units	Estimated Quantities	Unit Price	Total Est. Price
Remove Existing Wingwalls and Footings	EA	4	\$	\$
Install Precast Wingwall Footings	EA	4	\$	\$
Install Precast Wingwalls	EA	4	\$	\$
SUB TOTAL				\$

Ridgewood Drive Inlet Replacement

Bid Item	Units	Estimated Quantities	Unit Price	Total Est. Price
8' x 3' Inlet Top w/ MH	EA	1	\$	\$
Sidewalk (4' Wide)	SF	160	\$	\$
Curb (Throat)	LF	20	\$	\$
Asphalt Patch	SF	60	\$	\$
SUB TOTAL				\$

- | | |
|--------------------------------------|-----------------|
| 1. Crest Drive | Subtotal: _____ |
| 2. Olive/Jefferson Culvert | Subtotal: _____ |
| 3. Aspen Drive Culvert | Subtotal: _____ |
| 4. Silvertop Wingwalls | Subtotal: _____ |
| 5. Ridgewood Drive Inlet | Subtotal: _____ |
| 6. Traffic Control for all Sites | Subtotal: _____ |
| 7. Mobilization, Bonds and Insurance | Subtotal: _____ |

TOTAL BASE BID: _____

Total Base Bid for Project Number: 20-350-201

\$ _____

In blank above insert numbers for the sum of the bid.

(\$ _____)

In blank above write out the sum of the bid.

****REVISED** BID PROPOSAL FORM E – RFP 20-350-201
CONTINUED**

Company Name _____

By _____
Authorized Person's Signature

Print or type name and title of signer

Company Address _____

Phone _____

Fax _____

Email _____

Date _____

ADDENDA

Bidder acknowledges receipt of the following addendum:

Addendum No. _____

Addendum No. _____

Addendum No. _____

Addendum No. _____

Addendum No. _____

Addendum No. _____

LATE BIDS CANNOT BE ACCEPTED!

Ridgewood Drive Inlet Replacement

