

## CITY OF RAYMORE

100 Municipal Circle · Raymore, MO. 64083  
Phone · 816-892-3045 · Fax · 816-892-3093



### **ADDENDUM NO. 2**

Municipal Circle Detention Improvements  
Project #20-266-202

All plan holders are hereby notified and agree by signature below, that the proposal includes consideration of the following changes, amendments, and/or clarifications and costs associated with these changes and are included in the proposal.

### **Addendum No. 2 - Questions and Clarification.**

**1. Clarification:** Plan sheet P2 leaves the installation of the following items to the discretion of the engineer:

- 20 Mil Impermeable Liner Over Top of Pipe
- Bedding (note 3)
- Geotextile (note below note 7)

Can you please clarify as to whether or not these items will be required?

**Response:**

- 20 Mil Impermeable Liner Over the Top of Pipe is not required
- Bedding is required
- Geotextile is required

**2. Question:** What permits will be required for this work? Will the city be waiving permit fees?

**Answer:** The only permit required would be that the general contractor and any subs would have to have City Occupational Licenses. That fee will not be waived.

**3. Question:** What are the maintenance requirements on the landscaping & sod?

**Answer:** The contractor is expected to maintain the sod and landscaping until it becomes established. It's expected that there will be an irrigation system installed by the time the sod and landscaping are placed. If not, water is available from the City fire hydrants at no cost. Contractor would be responsible for providing hoses and sprinklers as needed.

**4. Question:** Who is responsible for onsite testing, if any (concrete slump/air, fill compaction, etc.)? If the contractor, what testing is being required?

**Answer:** The contractor is responsible for all testing. A gradation test of the gravel/backfill is required prior to placement to ensure that it meets the system requirements and compaction testing of the gravel/backfill as it's placed if required by the system's manufacturer. One slump/air/cylinder test will be required for concrete.

Any other questions regarding this proposal shall be submitted to Kim Quade, CPPB by email at kquade@raymore.com or by phone at (816) 892-3045. There will be no questions allowed after October 30, 2020 at 5 p.m.

I hereby certify that the above have been considered and associated costs have been included in this bid.

Company Name: \_\_\_\_\_

By: \_\_\_\_\_

Title: \_\_\_\_\_

Address: \_\_\_\_\_

City, State, Zip: \_\_\_\_\_

Date: \_\_\_\_\_ Phone: \_\_\_\_\_

Signature of Bidder: \_\_\_\_\_

**ADDENDUM MUST BE SUBMITTED WITH BID**