# NOTICE TO BIDDERS 2022 Street Overlay, Curb Replacement, Storm Sewer Project City of Raymore, Missouri

Sealed proposals will be received by the Purchasing Specialist at the City Hall, 100 Municipal Circle, Raymore, Missouri, until 10:00 a.m. on May 26, 2022. In accordance with the Missouri Sunshine Law, RSMo 610.021. Proposals will be opened on said date and time and only the bidder name and base proposal price will be read aloud. All other documents will be checked for responsiveness after Bid proposal opening. On all requests and correspondence, please reference RFP Number 22-012.

## **ANTICIPATED SCOPE OF SERVICES:**

### STREET OVERLAY

Two of the streets, Heritage and Calico, have storm sewer crossings and curb to be removed and replaced prior to being milled and overlaid.

- 58950 sq yds of full width milling
- 6645 tons of 2" Type 3 Recycled overlay
- Tack oil is to be UltraTack, Trackless Tack NTSS-1HM manufactured by Blacklidge applied at the residual rate of .06 gal/sq yd, CAT-TAC trackless tack manufactured by Hunt Refining applied at the same rate, or other approved trackless tack oil. Paving will not begin until the tack has broken.
- Milled surface is to be cleaned by a vacuum sweeper immediately prior to tacking.
- 1597 tons of full depth patching, Type 1 Recycled asphalt. Type II can be used on Hubach Hill, including surface.
- 2000 linear feet of deep crack repair on 18 streets.
- 10000 pounds of crack seal on two thoroughfares prior to micro surface
- 34980 sq yards of Type II micro surface on two thoroughfare streets; Foxridge and Lucy Webb.
- Re-striping two thoroughfare streets after micro surfacing.
- Install two, Paveway Systems, brick pattern crosswalks with 6" wide, white, thermoplastic borders. Asphalt is to be milled and overlaid 50 feet either side of the center of the crosswalks prior to the crosswalk being installed. See the crosswalk on Municipal Circle at Centerview as an example.
- Provide traffic control that meets MUTCD standards for all phases of the project.
- See map for specific streets.

### **CURB REPLACEMENT**

- 18000 linear feet curb removal and replacement with modified high back and roll back curb.
- 15 surface mount detectable warning tiles for ADA ramps.
- 8 ADA ramps

• 1000 square feet of sidewalk replacement

#### STORM SEWER

 Remove and replace 11 sections of storm sewer crossing two streets (Calico and Heritage) along with the adjacent curb inlets/junction boxes.

The specific locations of the work to be done shall be contained in the special provisions section of the bid document. The contractor shall bid on all work.

All equipment, material and workmanship must be in accordance with the Specifications and other Contract Documents. Project manual, plans and specifications, and proposal forms may be viewed at the office of the City Engineer, 100 Municipal Circle, Raymore, Missouri 64083.

Request for Proposal documents can be downloaded electronically for a non-refundable fee of \$15.00 at <a href="www.questcdn.com">www.questcdn.com</a> by inputting Quest Project Number 8163126 on the Project Search Page. Copies of the Request for Proposal documents may also be obtained by prospective bidders from the City of Raymore, Engineering Dept., for a non-refundable cost of \$30.00. You can contact Quest CDN at 1-952-233-1632 or <a href="mailto:info@questcdn.com">info@questcdn.com</a> for assistance with free membership registration, downloading and working with the electronic documents.

Bidder must be a plan holder with the City of Raymore or QuestCDN in order to bid on the project.

A copy of the 2016 City of Raymore 'Standard Contract Documents and Technical Specifications & Design Criteria for Utility and Street Construction' may be obtained from the City of Raymore Engineering Department for \$50.00 or may be downloaded at no cost from the City's website at <a href="https://www.raymore.com">www.raymore.com</a>

A pre-bid meeting will be held on May 17, 2022 at 10:00 a.m. at Raymore City Hall in the Council Chambers. Attendance at the pre-bid meeting is highly recommended but not required.

A bid bond or certified check from a surety or bank, approved by the Purchasing Specialist, in an amount equal to, or greater than, 5% of the maximum total bid price must accompany each proposal.

Contractor shall provide a ten (10) hour Occupational Safety and Health Administration (OSHA) construction safety program for all employees who will be on-site at the Project.

All wages paid for work under this contract shall comply with the requirements of the prevailing wage law of the State of Missouri, Missouri Public Law 294, Sec. 290.210 through 290.340, R.S. MO. 1969, as amended.

Pursuant to 610.021 RSMo, Item 12, all documents within a request for proposal (RFP) will become an open record to the public upon a negotiated contract being executed. All documents within a request for bid (RFB) become open record as soon as the bid is opened. Bidders and proposers should be aware that all documents within a submittal will become open records.

The Owner reserves the right to reject any or all proposals and to waive informalities or deficiencies therein. To negotiate with any or all bidders or others for more favorable terms or prices, and to award a contract to other than the bidder submitting the lowest cost bid proposal, with or without negotiation and to determine which is the lowest best and most responsive, to accept, at its option, any alternates and to approve the bond.